

**OFFICE OF THE KANGRA CENTRAL CO-OPERATIVE BANK LIMITED HEAD
OFFICE DHARAMSHALA DISTRICT KANGRA (H.P)-176215**

TENDER NOTICE

Sealed tenders on the items on rate basis for the following works are hereby invited from the eligible contractors to reach in the office of undersigned on or before 07th January, 2025 upto 12 noon. The same will be opened on the same day at 3:00 PM in the presence of intending contractors/ companies or their representatives who wish to be present.

Sr. No	Name of the work	Scope of Work	Tender Cost (Non-Refundable)	Earnest Money (Refundable)	Estimated Cost
1	Aluminium work for Banking Counters, Cabin Partition, panelling etc.	In the area of operation of the Bank i.e. in distt. Kangra, Una, Hamirpur, Kullu and Lahual & Spiti	3000/-	30000/-	Rs.3,00,000 approx. for each site
2	Networking, electrical work, earthing and other related works		3000/-	30000/-	Rs.1,70,000 approx. for each site
3	False Ceiling work with GRG (Glass fiber reinforced gypsum)		3000/-	30000/-	Rs.1,30,000 approx. for each site
4	Paint work and anti termite process		2500/-	10000/-	Rs.3,00,000 approx. for each site

Tender form containing details of work can be downloaded from the Bank website www.kccb.in on or before 06/01/2025 upto 5 PM. Earnest money and tender cost are in the shape of demand draft in favour of "The General Manager, The Kangra Central Co-operative Bank Ltd. Head office Dharamshala, (HP) 176215 must accompany with the tender. Tender without earnest money shall not be entertained. The above work will be awarded to the selected vendor as and when required by the Bank. Undersigned reserves the right to accept or reject any or all the tender without assigning any reason. Telegraphic or conditional tenders shall not be accepted.

-sd-

General Manager

TENDER

OFFICE OF THE KANGRA CENTRAL CO-OPERATIVE BANK LIMITED HEAD OFFICE DHARAMSHALA DISTRICT KANGRA (H.P)-176215

Name of the work :- Providing and fixing Aluminium Partitions, Banking Counters, Panelling, interior work etc. in the area of operation of the Bank i.e. in Distt. Kangra, Una, Hamirpur, Kullu, and Lahual & Spiti, Shimla.

Name of the contractor:-

1. Sealed items rates tenders are invited by the General Manager on behalf of The Kangra Central Co-operative Bank Ltd. Head office Dharamshala for the above mentioned work .
2. The tender which should be placed in sealed cover with the name of the work superscribed on the envelop will be received by the General Manager , The Kangra Central Co-operative Bank Ltd. Dharamshala upto 12:00 Noon on or before 7th Jan. 2025 and same will be opened on the same day at 3:00 PM in the presence of tenderer or authorized representative who wish to be present.
3. The tender Form can be downloaded from our website www.Kccb.in and an amount of Rs.3000/- (which is non-refundable) being the cost of Tender Form must accompany in shape of demand draft drawn in favor of the General Manager ,the Kangra Central Co-operative Bank Limited Head Office Dharamshla.
4. Earnest money amounting to Rs.30000/-in the form of demand draft drawn in favor of the General Manager ,The Kangra Central Co-operative Bank Limited Head Office Dharamshla . Must accompany with each tender
5. The work is to be execute in the area of operation of the Bank i.e. Distt. Kangra ,Una Hamirpur ,Kullu and Lahual&Spiti Shimla.
6. Special care should be taken to quote the rates in figure as well as in words.
7. The contractor should submit a list of work with its value which are under execution or have already been executed by him.
9. The time allotted for the completion of the work will be issued in the award letter for different works.
10. The right of acceptance of a tender in whole or any part of the tender will rest with the Kangra Central Co-operative Bank Limited Head Office Dharamshla who will not bound to accept the lowest tender and reserve the right to reject any of all the tenders received without assigning reason(s).
11. The rates to be quoted by the contractor given in the contract agreement shall be inclusive of all charges like carriage and all other taxes.
12. Income tax shall be deducted from the running bills as per rules and regulations of Income Tax.
13. On the acceptance of tender name of the accredited representative of the contractor who should be responsible for taking instructions from the site engineer.

14. Loss or damage in transit will be the responsibility of the supplier
15. If the sub standard material is used by the vendor then the Bank will not liable to pay the same.
16. The contractor will have to provide a photocopy of the GST number , pan number, Bank account Copy .
17. There shall be no over writing in the tender document and other papers submitted. All additions, alternations, deletions and cutting should be initialed with rubber-stamp (or seal) by the same person, who signs the tender document, failing which so, the tender may be rejected.
18. No advance payment will be made. Payment will be made after completion of the work.
19. The rates given in this tender will be valid for march 2028.

I/we hereby tender for execution of work specified in the under written memorandum with the term specified in the memorandum at the specified therein and in accordance to all respect with the specifications , drawing , design, and instruction in written referred to the agreement and condition of the DNIT.

Signature and Address of the Contractor

Name of the work :- Providing and fixing Aluminium Partitions, Banking Counters, Panelling etc. in the area of operation of the Bank i.e. in Distt. Kangra, Una , Hamirpur, Kullu, and Lahual & Spiti.

S. No.	Description	Unit	Rate
1	Providing and fixing Powder coated Aluminium work for door, windows, partitions, and ventilators with extruded built up standard tabular and other sections of approved make confirming to IS-733 and powder coated to required shade accordingly to IS 1808 (minimum powder coating at grade Ac's) fixed with rawl plugs and screws with fixing clip with expansion hold fasteners including filling up of gape at Junction at top, bottom and sides with required PVC neeprar felt etc. Aluminium section shall be smooth rust free straight mitered and joined mechanically wherever required including cleate, angles , aluminium shape beeding for glazing/ panrling , C.P. Brass / stainless steel screws all complete as per architectural drawing and directions of the engineer incharge, glazing and paneling to be paid separately for fixed portion with in all leads lifts and material and other incidental.	Kg.	
2	Providing and fixing powder caoted grill of required pattern on aluminium frames or windows etc. with aluminium flate, square or round bars with round headed bolts and nuts or by screws etc. complete with all leads & lifts or material and other incidental.	Sq. mtr.	
3	Providing & fixing pre laminated of three layer medium density (exterior grade) practical board shade -1 type-II confirms to IS-12725 bounded with phenol formaldehyde synthetic resin of approved brand and manufacture in panelling fixed in aluminium door, windows, shutters and pattern frames with CP Brass stainless steel & screws etc. complete as per architectural drawing and directions of Engineer incharge with all leads & lifts of material and other incidental. 12mm thick both sides. Sq. m	Sq. mtr	
4	Providing & fixing 19 mm thick commercial baord of approved quality, 2.5mm thick vaneer both sides joining with nails complete. (century or equivalent)	Sq. mtr	
5	Providing & fixing aluminium composite panneling 4mm thick with 0.5 mm aluminium skin thickness of required shade pattern and approval quality (Alstone or equivalent)	Sq. mtr	
6	Providing & fixing 0.8 mm thick sunmica of approved quality and shades with required adhesive, fevicol complete.	Sq. mtr	
7	Providing & fixing 6mm thick commercial ply of approved quality joining with nails and adhesive complete.	Sq. mtr	
8	Providing & fixing glassing in aluminium door, windows ventilators shutters and partitions etc. with PVC gasket etc. complete as per architectural drawing and the direction of	Sq. mtr	

	engineer incharge (cost of aluminium shape beading shall be paid separately) with glass panes 5.0 mm thick weight not less than 10 kg per sq. Mtrs. With in all lead, lifts and other incidental. (Modi Glass Saint Gobin or Equivalent)		
9	Providing & fixing 12mm thick plain glass with webbed edged in aluminium door, partitions etc. rubber gasket with in all leads and lifts (cost of aluminium)	Sq. mtr	
10	Providing & fixing floor door closer confirming to ISI specification and as per requirement and direction of Bank .	Each	
11	Providing & fixing hydraulic door closer ISI mark as per requirement with screws	Each	
12	Providing & fixing brass locks six leavers of approved quality 100 mm with necessary screws complete.	Each	
13	Providing & fixing American aluminium powder coated handle of approved quality with necessary screws.	Each	
14	Providing & fixing teak wood moulding of size 20 x12mm with necessary adhesive and nails.	Rmt.	
15	Providing & fixing powder coated aluminum tower bolts heavy of approved quality a) 150mm b) 200mm	Each	
16	Providing & fixing powder coated aluminium rubber door stopper of approved quality with screws complete.	Each	
17	Providing and fixing powder coated aluminium built hinges of approved quality with screws complete.	Each	
18	Painting two coats with ready mixed paint of approved quality with a coat of primer , filling sand papering on wood or wood based surface to give even finish.	Sq. mtr	
19	Polishing two or three coats of spirit polish on new wood based surface complete in all respect.	Sq. mtr	
20	Polish two or more coats of Melamine polish on old wood work.	Sq.mtr.	
21	Dismantling of old Counter,cashier cabin,Manager cabin,	Sq.mtr	
22	Refixing old material in counter,cashier cabin,manager cabin, as per requirement and direction of Bank .	Sq.mtr	
23	Providing and fixing Rubber Gasket in Refixing old aluminum door, windows, ventilators shutters and partitions etc	kg	
24	Powered coating for old aluminum Counter,cashier cabin ,manager cabin ,partitions work ,as per requirement and direction of Bank .	sq. mtr	
25	Providing & fixing glassing in aluminum door, windows ventilators shutters and partitions etc. with PVC gasket etc. complete as per architectural drawing and the direction of	Sq .mtr	

15	engineer in-charge (cost of aluminum shape beading shall be paid separately) with glass panes 8.0 mm thick weight not less than 16kg per sq. Mtrs. With in all lead, lifts and other incidental. (Modi Glass Saint Gobin or Equivalent)		
26	HDHMR Board 19 mm thick for modular almirah with 1mm thick mica and hydraulic hinges & telescopic channel soft close confirming to ISI specification and as per requirement and direction of Bank .	sq. mtr	
27	Providing & fixing wooden flooring (Actiontessa) as per requirement and direction of Bank .	Sq mtr	
28	Providing & fixing WPC wall paneling per requirement and direction of Bank .	Sq mtr	
29	Providing & fixing PVC paneling super sonic as per requirement and direction of Bank .	Sq mtr	
30	Providing & fixing aluminum composite paneling 5mm thick for partition uses required shade pattern and approval quality as per requirement and direction of Bank .	Sq mtr	
31	P/F PVC molding with necessary adhesive and nails etc.	Rmt.	

Signature and Address of the Contractor

